

CORPS OF ENGINEERS BALTIMORE MD BALTIMORE DISTRICT F/G 13/13  
NATIONAL DAM INSPECTION PROGRAM. VALLEY VIEW LAKE DAM (NDI ID N--ETC(U)  
FEB 81

**F/6 13/13**


NATIONAL DAM INSPECTION PROGRAM. VALLEY VIEW LAKE DAM (NDI ID N--ETC(U)  
FEB 81

NL

1. **2**

AD94057

7



AD A099057

SUSQUEHANNA RIVER BASIN  
TRIB. TO LITTLE FISHING CREEK, COLUMBIA COUNTY  
PENNSYLVANIA

VALLEY VIEW LAKE DAM

NDI ID No. PA-01006  
DER ID No. 19-75

VALLEY VIEW LAKE ASSOCIATION

PHASE I INSPECTION REPORT

6 NATIONAL DAM INSPECTION PROGRAM.

Prepared By:

DEPARTMENT OF THE ARMY  
Baltimore District, Corps of Engineers  
Baltimore, Maryland 21203

11 FEBRUARY 1981

"Original contains color  
plates. All DTIC reproduct-  
ion will be in black and  
white"

11-11111  
[unclear] is unlimited.

## **PREFACE**

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established guidelines, the spillway design flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. The spillway design flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition, and the downstream damage potential.

[illegible]

NDI ID No. PA-01006, DER ID No. 19-75

PHASE I INSPECTION REPORT

NATIONAL DAM INSPECTION PROGRAM

CONTENTS

<u>Description</u>	<u>Page</u>
Brief Assessment of General Condition and Recommended Action.....	iii
SECTION 1 - Project Information.....	1
SECTION 2 - Engineering Data.....	6
SECTION 3 - Visual Inspection.....	7
SECTION 4 - Operational Procedures.....	9
SECTION 5 - Hydrology and Hydraulics.....	10
SECTION 6 - Structural Stability.....	12
SECTION 7 - Assessment, Recommendations, and Proposed Remedial Measures.....	14

APPENDICES

<u>Appendix</u>	<u>Title</u>
A	Checklist - Visual Inspection.
B	Checklist - Engineering Data.
C	Photographs.
D	Hydrology and Hydraulics.
E	Plates.
F	Geology.

PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM

BRIEF ASSESSMENT OF GENERAL CONDITION  
AND  
RECOMMENDED ACTION

NAME OF DAM: Valley View Lake Dam  
NDI ID No. PA 01006  
DER ID No. 19-75

SIZE: Small (20 feet high; 72 acre-feet)

HAZARD CLASSIFICATION: High

OWNER: Valley View Lake Association  
Millville, PA

STATE LOCATED: Pennsylvania

COUNTY LOCATED: Columbia

STREAM: Tributary of Little Fishing Creek

DATE OF INSPECTION: 2 Dec 80

The visual inspection and review of available design and construction data indicate that Valley View Lake Dam is in poor condition. The deteriorated condition of the spillway walls, severe erosion of the spillway discharge channel, and seepage observed at the downstream toe are the primary deficiencies which cause concern for the safety of this facility. The dam in its present condition is considered to be unsafe, non-emergency.

The hydrologic and hydraulic computations indicate that the combination of reservoir storage and spillway discharge capacity will pass only 32% of the PMF prior to overtopping the embankment. Overtopping the dam could cause failure, which would lead to a significant increase in downstream loss of life and property damage. Therefore, the spillway for Valley View Lake Dam is considered to be seriously inadequate.

The following measures ~~are~~ recommended for immediate action: *are listed*

1. The owner should immediately retain a qualified professional engineer, experienced in dam design and construction, to determine remedial measures necessary for the damaged spillway and discharge channel, and to investigate means for providing adequate spillway capacity for this facility.


2. The seepage near the left abutment should be closely monitored, and appropriate remedial measures taken if any turbidity or significant increase in flow is noted.

Vally View Lake Dam

3. The erosion of the ditch along the left abutment contact on the downstream side of the embankment should be monitored, along with the associated minor cracking occurring adjacent to the ditch. Appropriate remedial measures should be taken if the condition worsens significantly.
4. The drop inlet should be provided with some form of protection from floating debris.
5. The bridge across the spillway should be removed or rehabilitated such that it will have no adverse impact on the spillway structure.
6. The upstream embankment face should be provided with adequate riprap protection.
7. The operational adequacy of the existing plug or valve on the upstream end of the outlet pipe should be verified.
8. A formal surveillance and downstream emergency warning system should be developed for use during periods of heavy or prolonged precipitation.
9. An operation and maintenance manual or plan should be prepared for use as a guide in the operation of the dam during normal and emergency conditions.
10. A schedule of regular inspection by a qualified engineer should be developed.

APPROVED BY:

DEPARTMENT OF THE ARMY  
BALTIMORE DISTRICT, CORPS OF ENGINEERS

  
DATE: 9 APR 81  
JAMES W. PECK  
Colonel, Corps of Engineers  
District Engineer

VALLEY VIEW LAKE DAM



OVERVIEW



PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM

VALLEY VIEW LAKE DAM

NDI ID No. PA01006  
DER ID No. 19-75

SECTION 1

PROJECT INFORMATION

1.1 General

a. Authority. The Dam Inspection Act, Public Law 92-367, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a program of inspection of non-federal dams throughout the United States.

b. Purpose. The purpose of this inspection is to determine if the dam constitutes a hazard to human life and property.

1.2 Description of Project.

a. Description of Dam and Appurtenances. Valley View Lake Dam is an earthfill structure approximately 20 feet high and 380 feet in length (including spillway). The spillway is an uncontrolled broad-crested weir located at the right abutment. A roadway bridge, no longer in service, spans the spillway, which has a length of 20 feet between two concrete walls. The outlet works consists of a 10 inch diameter concrete encased corrugated metal pipe (CMP) extending through the embankment, having a 15 or 18 inch diameter CMP drop inlet on the reservoir side. The drop inlet has a crest elevation of 656.0 which is 0.75 feet below the spillway crest elevation.

Available records indicate that the original design called for a dam height of 21.7 feet, with an overall length of 265 feet. The dam was to have a clay core, and the upstream slope was to be protected by riprap. The 10-inch outlet pipe was to be encased in 6 inches of concrete, with an anti-seep ring near the center of the embankment. The spillway bridge was not included in the original design.

Normal inflow is discharged through the outlet works.

b. Location. Greenwood Township, Columbia County  
U.S.G.S. Quadrangle - Millville.  
Latitude 41° 7.1' and Longitude 76° 31.0'  
Ref. Appendix E, Plates I & II.

c. Size Classification: Small: Height - 20.1 feet, Storage - 72 Acre-feet.

d. Hazard Classification: High (Refer to Section 3.1.E)

e. Ownership: Valley View Lake Association, c/o Jacob Kessler,  
Secretary/Treasurer R.D. #2, Millville, Pennsylvania 17846

f. Purpose: Recreation

g. Design and Construction History: The design and construction of the dam were both apparently accomplished primarily by Mr. Ernest Albertson, the original owner. Mr. Albertson was assisted by a Mr. Fought, who reportedly had some previous experience in the construction of small dams for the U.S. Soil Conservation Service.

A permit for construction of the dam was issued by the Pennsylvania Department of Environmental Resources (PennDER) on 30 June 1958, and construction was reported to be complete by Mr. Albertson on 16 August 1960.

During construction (6 November 1958), a PennDER inspector recommended that a change be made in the alignment of the spillway discharge channel to prevent erosion of the toe of the embankment. In a later PennDER inspection report dated 28 October 1959, it was stated that heavy rainfall just prior to the inspection had caused the predicted erosion to occur. Mr. Albertson was advised to place large boulders in the discharge channel and place a concrete apron just below the spillway. On 16 August 1960 Mr. Albertson advised PennDER that all requested work had been done and the dam was complete.

The PennDER permit for the dam was officially assigned to the Valley View Lake Association on 14 March 1969.

h. Normal Operating Procedure. The reservoir is normally maintained at the crest of the drop inlet. Inflow which exceeds the capacity of the drop inlet will be stored until reaching the uncontrolled spillway elevation.

### 1.3 Pertinent Data.

#### a. Drainage Area (square miles)

From files:	0.52
Computed for this report:	0.52
Use:	0.52

#### b. Discharge at Damsite (cubic feet per second)

Maximum known flood	unknown
Outlet works with maximum pool (El. 660.2)	12
Spillway with maximum pool (El. 660.2)	420

c. Elevations (feet above mean sea level)

Top of Dam	
Design	661.25
Existing (low point as surveyed)	660.20
Normal pool (design drop inlet crest)	656.00
Spillway Crest (used as datum)	
Design	656.75
Existing	656.75
Outlet Works	
Upstream portal invert (design)	641.5
Crest of Drop Inlet	
Design	656.0
Existing	656 (Estimated)
Downstream portal invert	
Design	639.6 +
Existing	641.9
Streambed at toe	640.1

d. Reservoir Length (feet)

Normal pool (El. 656.00)	1500
Spillway crest (El. 656.75)	1600
Maximum pool (El. 660.2)	1800

e. Storage (acre-feet)

Normal pool (El. 656.00)	30
Spillway crest (El. 656.75)	35
Maximum pool (El. 660.2)	72

f. Reservoir Surface (acres)

Normal pool (El. 656.00)	9.0
Spillway crest (El. 656.75)	9.5
Maximum pool (El. 660.2)	13.0

g. Dam

Note: Refer to plates in Appendix E for plans and sections.

<u>Type</u>	Earthfill w/clay core
<u>Length</u>	380 feet (incl. spillway)
<u>Top Width</u>	10 feet (as surveyed; 12 feet design)

g. Dam (Cont'd):

Height

20.1 feet (as surveyed; low pt. to d/s toe)

Side Slopes

Upstream  
Downstream

1V:3H  
1V:3H

Zoning

8 foot wide clay core to El. 656.0 (design)

Cutoff

Clay core designed to extend to solid shale; 4 feet below existing ground.

Grouting

None reported.

h. Outlet Works.

Type

Ten-inch diameter concrete encased corrugated metal pipe through embankment for pond drain; attached 15 or 18 inch corrugated metal pipe as a drop inlet.

Closure

Glass bottle on upstream end, no control on drop inlet.

i. Spillway

Type

Uncontrolled, rectangular concrete broad crested weir

Location

Right end of dam

Length

20 feet

Crest Elevation

656.75 (from design dwgs.)

Freeboard

3.5 feet

i. Spillway (Cont'd):

Approach Channel

Reservoir

Downstream Channel

Earth and Rock

Bridge

Low steel at elev.  
660.55, no piers

## SECTION 2

### ENGINEERING DATA

#### 2.1 Design.

The available data for Valley View Lake Dam consist of files provided by PennDER. Information available includes a permit application report with a general description of the proposed design, PennDER inspection reports, various related correspondence, and line sketches dated April and May 1958 showing a cross-section, general plan, and longitudinal section of the proposed dam.

No other plans or design details are known to exist.

#### 2.2 Construction.

Information relative to the construction of the dam consists of PennDER inspection reports dated 6 November 1958, 6 July 1959, and 28 October 1959.

These reports indicate that the overall construction of the dam was satisfactory; however, the potential erosion problems with the alignment of the spillway discharge channel being so close to the toe of the embankment were noted. The original owner was to have corrected this problem by protecting the channel with large boulders and placing a concrete apron at the downstream side of the spillway.

The July 6, 1959 report also indicates that riprap was placed on the upstream slope.

#### 2.3 Operation

No formal records of operation or maintenance exist. Members of the Lake Association live in homes surrounding the lake and are responsible for operation and maintenance of the facility. Mr. Jacob Kessler, Secretary-Treasurer of the Association, stated that to his knowledge the greatest spillway flow occurred during Tropical Storm Agnes in 1972 when the lake rose to within approximately one foot of the dam crest.

Mr. Kessler did not recall any riprap ever being visible on the upstream slope of the dam.

The most recent PennDER inspection (May 1964) indicated that the dam was in satisfactory condition.

#### 2.4 Evaluation

a. Availability. All available written information was contained in the permit files provided by PennDER.

b. Adequacy. The available data, including that collected during the recent detailed visual inspection, are considered to be adequate to make a reasonable assessment of the dam.

## SECTION 3

### VISUAL OBSERVATIONS

#### 3.1 Observations.

a. General. The overall condition of the dam and its appurtenances is poor.

Noteworthy deficiencies are described briefly below. The visual inspection checklist and field sketch are presented in Appendix A of this report. Photographs taken during the inspection are reproduced in Appendix C.

The reservoir pool was approximately 0.2 feet above normal pool (El. 656.00) on the day of the inspection, 2 December 1980. The owner's representative was not present during the inspection but was interviewed at his nearby residence.

b. Embankment. The horizontal alignment of the dam is good; however a crack, about 40 feet long, is forming on the downstream face near the left abutment. The junction of the dam and left downstream abutment form a drainage channel which is eroding and causing the adjacent embankment to slough sufficiently to form the crack. A large clump of briars is growing upslope of the crack. The downstream face and the upper 18 inches of the upstream face are grass covered. The crest, which is used as a roadway, and the remainder of the upstream face are covered with small gravel and shale bedding respectively. Trees and brush are growing along the downstream abutment contacts. Clear seepage is flowing at the rate of about 8 gpm from two locations at the toe between the midpoint of the dam and the left abutment contact. The source is unknown but may be springs since the lake is reported to be spring-fed. The vertical alignment of the crest is fair, with a maximum variation of 0.7 feet; however the low point which is located at the dam's right center is one foot below the design crest elevation of 661.25.

c. Appurtenant Structures. The location of the outlet works and the spillway are shown on the field sketch in Appendix A. The spillway approach channel is the reservoir with approximately the first 20 feet being grass covered. The spillway slab and walls are cracked and in poor condition. The left spillway wall is separated from the upstream wingwall and is tilting. Based on photographs in PennDER files, the right spillway wall was originally constructed to the same height as the left wall. Sometime after April 1964 the right wall was raised about 3 feet by placing concrete block with mortared joints on top of the existing wall. A 4 foot high by 6 foot long triangular section of this concrete block has failed. The remaining concrete block is leaning and separating at the mortared joints. The upstream end of the original concrete wingwall is also seriously cracked and leaning. Concrete in the form of a bulge is visible beneath the bridge and acts as a buttress for the right wall. The spillway walls and slab end approximately 4 feet downstream of the bridge. Material from the right abutment is covering a portion of the right side of the slab to a maximum depth of 2 feet.

The area immediately downstream of the spillway slab is filled with dumped trees, brush and leaves which prevent a thorough inspection of the area. This debris was probed and it is apparent that erosion has created a 12 to 15 foot vertical drop from the spillway slab. The depth of the observed undercutting of the slab could not be determined due to the heavy debris. The right side of the discharge channel has a near vertical slope in weathered shale to a height of 8 feet for the first 50 feet before becoming steeply sloping earth. The initial 50 feet of the channel bottom is also cut into bedrock. Further downstream the bottom is lined with fragments of bedrock that have eroded from the upper portion. Erosion of the left side of the discharge channel is removing material from the dam embankment. Several large pieces of broken concrete line the upper portion of the channel slope but afford little protection. As the channel turns and parallels the toe of the dam, the left side is eroded on a slope of 4V on 3H to a height of 5 feet.

The discharge end of the 10 inch diameter outlet conduit and the top of the drop inlet are the only portions of the outlet works that were observed. The drop inlet is uncontrolled and appears to be about a 15 or 18 inch diameter corrugated metal pipe. A trashrack consisting of several metal rods attached to the pipe has collected some debris which was partially obstructing flow. On the day of inspection the structure was operating with approximately 0.2 feet of head. The outlet pipe projects 15 inches from the concrete encasement which in turn projects 2 feet from the embankment. The pipe is in fair condition. It should be noted that the design drawings show a 10 or 12 inch steel oil line placed on a concrete cradle and encased in 6 inches of concrete. The outlet pipe discharges into a small plunge pool, which is lined with 4-10 inch rock. Minor erosion is in evidence adjacent to the embankment. The earth lined discharge channel parallels the toe for a short distance before joining the natural streambed.

d. Reservoir Area. The reservoir slopes are moderate to steep and appear stable. Several residences are at various elevations around the entire perimeter of the lake.

e. Downstream Channel. The downstream channel is cut in earth and flows through meadowland in a relatively narrow floodplain for the first 1,000 feet. The floodplain then begins to widen and the stream crosses two local roads. Approximately 4,200 feet downstream from the dam, the stream crosses Pa. Route 42. Two houses are located adjacent to the stream 500 feet further downstream. The proximity of these residences to the stream constitutes a high hazard to loss of life should the dam fail.

f. Evaluation. The poor condition of the spillway walls and the severe erosion of the spillway discharge channel cause concern for the stability of the dam during high spillway discharges. Failure of the spillway walls could block the spillway and seriously reduce its capacity. The seepage at the toe causes less concern since no fines are being transported at this time; however this condition should be monitored. In addition, the erosion of the ditch along the left downstream abutment contact should be controlled and the crack monitored.



## SECTION 4

### OPERATIONAL PROCEDURES

4.1 Normal Operating Procedure. The lake is maintained at the level of the drop inlet, elevation 656.0. Inflow in excess of the capacity of the drop inlet is stored until the pool level reaches elevation 656.75, the spillway crest. Above this elevation spillway flow begins and discharges into an unnamed tributary of Little Fishing Creek. No formal operations manual exists.

4.2 Maintenance of Dam. The overall condition of the dam and appurtenances as observed by the inspection team was poor. The drop inlet was operating but had become partially obstructed by debris covering a portion of the inlet pipe. The spillway structure has deteriorated and the walls have tilted to a degree that now requires corrective action. Basic maintenance such as mowing the embankment and removing brush and trees has generally been performed. No formal maintenance manual exists.

4.3 Maintenance of Operating Facility. See Section 4.2 above.

4.4 Warning System. No formal warning system exists.

4.5 Evaluation. Overall maintenance of the facility appears to be inadequate at this time. The spillway has undergone significant deterioration, especially the wingwalls and spillway exit channel immediately downstream of the spillway crest. Investigation as to the type of closure on the drawdown facility should be determined and reviewed for adequacy and ease of operation under extreme conditions. Formal operation and maintenance manuals are recommended to ensure that all needed maintenance is identified and performed regularly. In addition, a formal warning system for the protection of downstream inhabitants should be developed. Included in the plan should be provisions for around-the-clock surveillance of the facility during periods of unusually heavy precipitation.

## SECTION 5

### HYDROLOGIC/HYDRAULIC EVALUATION

5.1 Design Data. No design reports, calculations or miscellaneous design data are known to exist for the facility. However, a suggested design spillway outlet capacity of 500 cfs was found in the PennDER files dated May 1958.

5.2 Experience Data. Records of reservoir levels and/or spillway discharges are not available. Overtoppings are not known to have occurred. Records of past performance are limited to the verbal report by the owner's representative concerning the June 1972 flood event.

5.3 Visual Observations. On the date of the inspection, conditions were present that may prevent the facility from operating as designed during a flood event. The spillway walls have deteriorated and are now leaning into the spillway opening. Immediately, downstream of the spillway slab, erosion has scoured out portions of the downstream channel adjacent to the embankment. This area had been filled with leaves and brush. Although this material presents no obstruction to flow, it did prevent a thorough inspection of the outlet channel. See Exhibit A-1 of Appendix A.

5.4 Method of Analysis. The facility has been analyzed in accordance with procedures and guidelines established by the U.S. Army, Corps of Engineers, Baltimore District for Phase I hydrologic and hydraulic evaluations. This analysis has been performed using a modified version of the HEC-1 program developed by the U.S. Army Corps of Engineers, Hydrologic Engineering Center, Davis, California. Capabilities of the program are briefly outlined in the preface contained in Appendix D.

#### 5.5 Summary of Analysis.

a. Spillway Design Flood (SDF). In accordance with the procedures and guidelines contained in the National Guidelines for Safety Inspection of Dams for Phase I Investigations, the SDF for Valley View Lake Dam ranges between one-half the Probable Maximum Flood (PMF) and the full PMF. This classification is based on the relative size of the dam (small), and the potential hazard of dam failure to downstream development (high). Due to the small storage (approximately 70 ac-ft) and small height (20 feet) the SDF selected was one-half PMF.

b. Results of the Analysis. Valley View Lake Dam was evaluated under near-normal operating conditions. The starting lake elevation was set at the drop inlet crest, El. 656.0, and the 20 foot wide emergency spillway is at elevation 656.75. The spillway crest to top of dam (low point) has a freeboard of approximately 3.5 feet. Flood hydrographs and spillway calculations were developed and the following results were obtained.

Spillway Capacity at Top of Dam	370 CFS
Peak SDF (1/2 PMF) Inflow	650 CFS

The overtopping analysis (using HEC-1DB) indicated that the discharge/storage capacity of Valley View Lake Dam is 32% of the PMF prior to overtopping the embankment. Under one-half PMF conditions, the dam is overtopped for 4.0 hours to a maximum depth of 0.8 feet. Since the SDF for this dam is one-half PMF, it can be concluded that Valley View Lake Dam has a high potential for overtopping, and thus, for breaching by floods of less than SDF magnitude.

To determine if the spillway is seriously inadequate, these conditions must be met:

- (i) There is a high hazard to loss of life from large flows downstream of the dam.
- (ii) The spillway is not capable of passing one-half PMF without overtopping the dam and causing failure.
- (iii) Dam failure resulting from overtopping would significantly increase the hazard to loss of life downstream of the dam from that which would exist just before overtopping.

Since Valley View Lake Dam meets the first two conditions, the third condition must be evaluated and therefore, a breach analysis was performed.

The modified HEC-1, computer program was used for the breaching analysis. The computer program requires that a failure elevation be given to the model so that failure may commence. It was assumed that the dam could withstand up to 0.5 feet of overtopping for short durations. Therefore, the water surface elevation selected to cause failure was elevation 660.7.

Four breach models were analyzed under conditions that would approximate 0.5 feet of overtopping. The flood selected to cause breaching was 42% of the PMF. Of the four plans, Plan 1 was a non-breach analysis used to provide a means of direct comparison between failure and non-failure conditions at downstream locations for the same flood event. Failure times in the three remaining plans were 0.33 hr (Plan 2), 1.00 hr (Plan 3), and 2.00 hrs (Plan 4). Downstream damage elevations and locations are shown in Appendix D and E of this report. Page D-14 of Appendix D, provides peak outflows and changes in stage at downstream damage centers. As indicated in the table, failure conditions significantly increase the hazard to loss of life when compared to non-failure conditions. Breach geometry and location are also discussed in Appendix D.

**5.6 Spillway Adequacy.** Under existing conditions Valley View Lake Dam can accommodate 32% of the PMF prior to overtopping. Should an event in excess of this occur, the dam would be overtopped and could possibly fail. Since the failure of this dam increases the hazard to loss of life or property damage at existing downstream residences, this spillway is considered to be seriously inadequate. The dam can accommodate 47% of the PMF if the embankment is raised to the design elevation of 661.25.

## SECTION 6

### STRUCTURAL STABILITY

#### 6.1 Evaluation of Structural Stability

##### a. Visual Observations

(1) Embankment. Visual observations of Valley View Lake Dam indicate that the dam and appurtenances are in poor condition. The embankment is apparently constructed of random earth. Surface soil on the upstream slope was visually classified as silt, ML; soil on the downstream slope was visually classified as clay, CL. The upstream and downstream slopes measured 3H:1V as designed; however, the crest width measured 10 feet which is 2 feet less than design. There is no riprap on the upstream embankment face even though there appears to be bedding below the water. A footpath of shale, approximately 4 feet wide, along the upstream face may offer some resistance to erosion. No erosion was noted on the upstream slope. Drainage from the ditch located at the downstream left abutment contact is causing erosion of the embankment toe. The embankment adjacent to the ditch is wet and shows signs of movement. There appears to be a crack developing in the embankment parallel to the drainage ditch and approximately 8 feet away. The right downstream embankment toe is being eroded by spillway discharges since the spillway channel is at the abutment contact. Erosion has steepened some areas of the embankment toe to a slope of 3H:4V. Clear seepage was observed at the toe and left downstream abutment contact with a combined discharge of approximately 8 gpm.

(2) Appurtenant Structures. The spillway is in poor condition. Both walls are leaning inward. A portion of the upstream end of the right wall has collapsed. A bridge for limited vehicle traffic spans the spillway and rests on both walls, which contributes to the instability of these walls.

The spillway channel lacks protection and has experienced a large amount of erosion in the weathered shale exposed in the first 50 feet of the channel. The downstream end of the spillway slab has been undetermined and a near vertical 12 to 15 foot drop has been caused by erosion.

##### b. Design and Construction Data

(1) Embankment. Design and construction data consist of several sketches, a permit application, and several letters. No stability analyses, permeability tests, or soil strength tests are known to have been performed. Three test pits were dug in the dam foundation and show loam overlying clay which overlies shale. The dam was designed to have an 8 foot wide clay core excavated to shale and a top elevation 656.0. The permit application indicates that the embankment was to be placed and compacted in 4 inch lifts, have a crest width of 12 feet and up and downstream slopes of 3H:1V. The upstream slope was riprapped for protection.

(2) Appurtenant Structures. Design and construction data are listed in paragraph 6.1b(1). The existing outlet works consists of a concrete

encased 10 inch CMP sealed on the upstream end. It is in fair condition. A 15 or 18 inch vertical pipe is connected to the 10 inch CMP. The spillway located at the right end of the embankment is constructed of concrete, located on natural ground, and designed to have upstream and downstream cutoffs. Eight inch stones were to be placed in the downstream spillway channel for the first 20 feet.

c. Operating Records. None.

d. Post Construction Changes. No changes have been reported to PennDER; however, changes have been made. A bridge was constructed over the spillway. The trash rack originally provided for the drop inlet has been replaced. Riprap originally placed on the upstream slope has been removed.

e. Seismic Stability. The embankment is located in Seismic Zone 1 and is considered to be statically stable. Normally, it can be considered that if a dam located in this zone is stable under static conditions, it can be assumed safe under minor earthquake conditions. The spillway walls do not appear to be stable and could possibly fail with earthquake loading.

## SECTION 7

### ASSESSMENT AND RECOMMENDATIONS

#### 7.1 Dam Assessment

a. Safety. The visual inspection and review of available design and construction data indicate that Valley View Lake Dam is in poor condition. The deteriorated condition of the spillway walls, severe erosion of the spillway discharge channel, seepage observed at the downstream toe, and limited spillway capacity are the primary deficiencies which cause concern for the safety of this facility. The dam in its present condition is considered to be unsafe, non-emergency.

The hydrologic and hydraulic computations indicate that the combination of reservoir storage and spillway discharge capacity will pass only 32% of the PMF prior to overtopping the embankment. Therefore, in accordance with the criteria outlined and evaluated in Section 5.5, the spillway for Valley View Lake Dam is considered to be seriously inadequate.

b. Adequacy of Information. The design and construction data contained in PennDER files in conjunction with data collected during the recent visual inspection, are considered to be adequate for making a reasonable assessment of this dam.

c. Urgency. The recommendations presented below should be implemented immediately.

d. Necessity for Additional Studies. The results of this inspection indicate a need for additional studies to provide an adequate spillway facility for this dam, including design of necessary remedial measures for the existing wingwalls and discharge channel.

#### 7.2 Recommendations.

1. The owner should immediately retain a qualified professional engineer, experienced in dam design and construction, to determine remedial measures necessary for the damaged spillway and discharge channel, and to investigate means for providing adequate spillway capacity for this facility.

2. The seepage near the left abutment should be closely monitored, and appropriate remedial measures taken if any turbidity or significant increase in flow is noted.

3. The erosion of the ditch along the left abutment contact on the downstream side of the embankment should be monitored, along with the associated minor cracking occurring adjacent to the ditch. Appropriate remedial measures should be taken if the condition worsens significantly.

4. The drop inlet should be provided with some form of protection from floating debris.

5. The bridge across the spillway should be removed or rehabilitated such that it will have no adverse impact on the spillway structure.

6. The upstream embankment face should be provided with adequate riprap protection.

7. The operational adequacy of the existing plug or valve on the upstream end of the outlet pipe should be verified.

8. A formal surveillance and downstream emergency warning system should be developed for use during periods of heavy or prolonged precipitation.

9. An operation and maintenance manual or plan should be prepared for use as a guide in the operation of the dam during normal and emergency conditions.

10. A schedule of regular inspection by a qualified engineer should be developed.

APPENDIX A

CHECKLIST - VISUAL INSPECTION



Check List  
Visual Inspection  
Phase 1

Name Dam Valley View Lake Dam County Columbia State Pennsylvania

Date(s) Inspection 2 Dec 80 Weather Sunny Temperature 50°

Pool Elevation at Time of Inspection 656.2 M.S.L. Tailwater at Time of Inspection 640.2 M.S.L.

Inspection Personnel:

J. Bianco (COE) E. Hecker (COE)

B. Cortright (COE) D. Kahler (PennDER)

J. Evans (COE)

B. Cortright Recorder

# EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS
Any noticeable seepage	A total of approximately 8 gpm of clear seepage is flowing from two locations at the toe. See Exhibit A-1 for location. Source could be springs but further monitoring is needed.
Junction of Embankment With: Abutments Spillway	Drainage along downstream left junction has created ditch which is eroding and causing a crack to form in embankment (see below). Left spillway wall is leaning in toward spillway but present effect on embankment is minimal; however failure of this wall would permit erosion of dam.
Surface Cracks	40 foot long crack is developing along downstream face parallel to the embankment/abutment contact and 7-8 feet upslope of the contact. A drainage ditch has formed along this junction with erosion causing sloughing of embankment.
Crest Alignment: Vertical Horizontal	Vertical - Good; maximum variation of 0.7 feet Horizontal - Good
Unusual Movement or Cracking at or Beyond the Toe	None observed.

# EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS
Sloughing or Erosion: Embankment Crest/Slopes Abutment Slopes	Runoff along downstream left junction of embankment and abutment is causing erosion of contact and dam. Ditch should be lined with rock or paved. See related items on Exhibit A-1. Spillway flow is eroding some of the embankment immediately downstream of the left spillway wall and along the toe of dam where discharge channel parallels toe. Concrete paving apparently was placed to protect area downstream of left spillway wall but this has been undermined and has broken into several large pieces.
Riprap Failures	Although design drawings specify riprap on upstream face, none exists at this time. A bedding type material presently covers most of the upstream face. No erosion problems apparent.
Miscellaneous Vegetation Roads or ramps	Upper 18 inches of upstream face and entire downstream face are grass. Roadway across crest surfaced with fine shale - good condition. Ramp down to spillway approach - no erosion; grass covered. Trees and brush along most of downstream embankment/abutment contact. Tree stump on upstream face-left side.
Instrumentation	None.
Staff Gage and Recorder	None.

# OUTLET WORKS

VISUAL EXAMINATION OF	OBSERVATIONS
Outlet Conduit	10 inch diameter corrugated metal pipe. Also a 15 or 18 inch diameter corrugated metal riser pipe (drop inlet) extends from the 10 inch pipe about midway on upstream slope.
Intake Structure Pond Drain Riser pipe (drop inlet)	Pond drain - Submerged; not observed. Riser pipe - Several metal bars across top act as trash rack. Partially blocked by leaves, twigs and small logs (firewood size)
Outlet Structure	None. Pipe projects about 15 inches beyond concrete encasement.
Outlet Channel	Small plunge pool at end of pipe which projects 2 feet beyond embankment. 4"-10" stone in plunge pool. Flows parallel to toe in earth channel for a short distance before joining natural stream channel.
Emergency Gate	None; upstream end of pipe reported sealed with glass bottle. Not observed.

# UNGATED SPILLWAY


VISUAL EXAMINATION OF	OBSERVATIONS
Concrete Weir	<p>Concrete slab; broad crested. Minor cracking. Left wall leaning in toward spillway. Joint w/upstream wingwall separated.</p> <p>Right wall near collapse. Poured concrete portion of wall and wingwall upstream of bridge are cracked through and leaning. The bridge is resting on five courses of concrete block which were placed on top of wall. Horizontal joints are missing some mortar and block is leaning in. Concrete has been poured against block and wall under bridge in form of bulge to buttress wall.</p>
Approach Channel	Reservoir; no obstructions.
Discharge Channel	<p>Deeply eroded; 12-15 foot vertical drop off end of spillway. Area filled recently with leaves which obscured thorough investigation; however it appears the spillway slab is being undercut. Dam embankment on left side immediately downstream of slab is eroding. Concrete apparently was placed to prevent erosion but undercutting has caused this paving to break-up into several large pieces. First 50 feet beyond spillway slab has bottom and vertical right side in bedrock. Left side is eroded embankment. Channel follows toe of dam with bedrock disappearing. Toe of embankment is eroded to slope of 3V:4H. Needs protection.</p>

# RESERVOIR

VISUAL EXAMINATION OF	OBSERVATIONS
Slopes	Moderate to steep; appears stable.
Sedimentation	None observed or reported.

# DOWNSTREAM CHANNEL

VISUAL EXAMINATION OF	OBSERVATIONS
Condition (Obstructions, etc.)	Earth bottom; Pa. Route 42 crosses 4,200 feet downstream
Slopes	Moderate side slopes; meadow
Approximate Number of Homes	Two homes near stream 4,700 feet downstream




PHASE I INSPECTION REPORT  
 NATIONAL DAM INSPECTION PROGRAM  
 VALLEY VIEW LAKE DAM  
 VALLEY VIEW LAKE ASSN.

FIELD SKETCH


EXHIBIT A-1





### TOP OF DAM - PROFILE

HORIZ.: 1 IN. = 50 FT.  
SCALE - VERT.: 1 IN. = 5 FT.



### EMBANKMENT SECTION

SCALE: 1 IN. = 30 FT.

### SPILLWAY SECTION

SCALE: 1 IN. = 30 FT.

PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM  
VALLEY VIEW LAKE DAM  
VALLEY VIEW LAKE ASSN.

### PROFILE AND SECTIONS

APPENDIX B

CHECKLIST - ENGINEERING DATA

CHECK LIST  
ENGINEERING DATA  
DESIGN, CONSTRUCTION, OPERATION  
PHASE I


<u>ITEM</u>	<u>REMARKS</u>
As-Built Drawings	None. However, sketches of dam from Penn Der Files are in Appendix E.
Regional Vicinity Map	U.S.G.S Millville Quadrangle 7 1/2 minute Quad Sheet. See Appendix E, Plate E-2.
Construction History	Permit issued in 1958, completed in 1960. Suggestion made to realign.
Typical Sections of Dam	See sketches in Appendix E.
Outlets - Plan Details Constraints Discharge Ratings	See sketches in Appendix E.
Rainfall/Reservoir Records	None
Design Reports	None
Geology Reports	None

<u>ITEM</u>	<u>REMARKS</u>
Design Computations Hydrology & Hydraulics Dam Stability Seepage Studies	None, however, Penn Der suggested a spillway design with a capacity of 500 c.f.s.
Materials Investigations Boring Records Laboratory Field	Three test pits were dug in dam foundation.
Post-Construction Surveys of Dam	None
Monitoring Systems	None
Modifications	Riprap appears to have been removed from upstream face. A bridge was constructed over the spillway, trash rack removed.
High Pool Records	In June 1972, pool was within 1 foot of dam crest.
Post-Construction Engineering Studies and Reports	None
Prior Accidents or Failure of Dam Description Reports	None reported. Erosion has taken place on spillway outlet channel adjacent to embankment; concrete protection has been undermined.

<u>ITEM</u>	<u>REMARKS</u>
Maintenance Operation Records	None
Spillway Plan	See Appendix E for sketches of spillway.
Sections Details	
Operating Equipment Plans & Details	None
Specifications	None
Miscellaneous	None
Previous Inspections	Last documented inspection in PennDer files was in 1964.

APPENDIX C

PHOTOGRAPHS



Valley View Lake Dam




1. Embankment Crest and Right Abutment



2. Upstream Face and Right Abutment



\*  $\frac{1}{2}$  is not an integer, so the slope is  $\frac{1}{2}$ , and the point  $\left(\frac{1}{2}, 0\right)$  is not on the line.



5. Approach Channel to Spillway



6. Close-up View of Downstream End Right Spillway Wall

Valley View Lake Dam



7. Crack in Approach Wall of Left Spillway Wall



8 Spillway Discharge Channel

Valley View Lake Dam



9. Downstream Channel



10. Drop inlet in Reservoir

Valley View Lake Dam



11. Outlet Conduit at  
Downstream Toe of Embankment



12 Drainage Channel Along Downstream Slope of Embankment  
Near Toe of Dam

Valley View Lake Dam



13. View of Downstream Slope. Clipboard indicates location of seepage.



14. Downstream Damage Area. First Floor Level is 5 Feet Above Streambed.

APPENDIX D

HYDROLOGY AND HYDRAULICS

## PREFACE

The modified HEC-1 program is capable of performing two basic types of hydrologic analyses: 1) the evaluation of the overtopping potential of the dam; and 2) the estimation of the downstream hydrologic-hydraulic consequences resulting from assumed structural failures of the dam. Briefly, the computational procedures typically used in the dam overtopping analysis are as follows:

- a. Development of an inflow hydrograph(s) to the reservoir.
- b. Routing of the inflow hydrograph(s) through the reservoir to determine if the event(s) analyzed would overtop the dam.
- c. Routing of the outflow hydrograph(s) from the reservoir to desired downstream locations. The results provide the peak discharge(s), time(s) of the peak discharge(s), and the maximum stage(s) of each routed hydrograph at the downstream end of each reach.

The evaluation of the hydrologic-hydraulic consequence resulting from an assumed structural failure (breach) of the dam is typically performed as shown below.

- a. Development of an inflow hydrograph(s) to the reservoir.
- b. Routing of the inflow hydrograph(s) through the reservoir.
- c. Development of a failure hydrograph(s) based on specified breach criteria and normal reservoir outflow.
- d. Routing of the failure hydrograph(s) to desired downstream locations. The results provide estimates of the peak discharge(s), time(s) to peak and maximum water surface elevations of failure hydrographs for each location.



HYDROLOGY & HYDRAULIC ANALYSIS  
DATA BASE

NAME OF DAM: VALLEY VIEW LAKE DAM

PROBABLE MAXIMUM PRECIPITATION (PMP) = 22.2 INCHES/24 HOURS (1)

SUSQUEHANNA RIVER BASIN

STATION	1	2	3
STATION DESCRIPTION	VALLEY VIEW LAKE DAM		
DRAINAGE AREA (SQUARE MILES)	0.52		
CUMULATIVE DRAINAGE AREA (SQUARE MILES)	0.52		
ADJUSTMENT OF PMF FOR (1) DRAINAGE AREA LOCATION (%)	100%		
6 Hours	117		
12 Hours	127		
24 Hours	136		
48 Hours	143		
72 Hours	145		
SNYDER HYDROGRAPH PARAMETERS			
Zone (2)	13		
C <sub>p</sub> (3)	0.5		
C <sub>p</sub> <sup>p</sup> (3)	1.85		
L <sup>t</sup> (MILES) (4)	1.29		
L <sub>ca</sub> (MILES) (4)	0.53		
tp = C <sub>t</sub> (L · L <sub>ca</sub> ) 0.3 (HOURS)	1.65		
SPILLWAY DATA			
CREST LENGTH (FEET)	20		
FREEBOARD (FEET)	3.5		

(1) HYDROMETEOROLOGICAL REPORT # , U. S. Army Corps of Engineers, 1955.

(2) Hydrologic zone defined by Corps of Engineers, Baltimore District, For Determination of Snyder Coefficients (C<sub>p</sub> and C<sub>t</sub>).

(3) Snyder Coefficients

- (4)  $L$  = Length of longest watercourse from dam to basin divide.  
 $L_{ca}$  = Length of longest watercourse from dam to point opposite basin centroid.

SUBJECT DAM SAFETY ANALYSISCOMPUTATIONS VALLEY VIEW LAKE

SHEET

SHEET

COMPUTED BY JPL

CHECKED BY

DATE

11-81

DAM CLASSIFICATION

SIZE OF DAM - SMALL

HAZARD - HIGH

REQUIRED SDF - 2 PMF TO FULL PMF

DAM STATISTICS

HEIGHT OF DAM - 21.1 FT

STORAGE AT NORMAL POOL - 30 AC-FT

STORAGE AT TOP OF DAM - 72 AC-FT

DRAINAGE AREA ABOVE DAMSITE - 0.52 mi<sup>2</sup>ELEVATIONS:

TOP OF DAM LOW POINT (FIELD) - 660.20

NORMAL POOL - 656.10

STREAMBED AT CENTERLINE OF DAM - 656.00

DROP INLET:

INLET - 656.20

OUTLET - 641.10

SPILLWAY CREST - 656.75

HYDROGRAPH PARAMETERS:

RIVER BASIN - SUSQUEHANNA RIVER BASIN

ZONE - 13

SYNDER COEFFICIENTS -

 $C_p = 0.50$  $C_e = 1.85$ 

MEASURED PARAMETERS: \*

 $L = \text{LENGTH OF LONGEST WATERCOURSE} \quad L = 12.9 \text{ mi}$  $L_{CA} = \text{LENGTH OF LONGEST WATERCOURSE TO CENTROID OF THE BASIN} \quad L_{CA} = 0.53 \text{ mi}$ \* FROM U.S.G.S. QUAD SHEETS ENTITLED: LAIRDSDVILLE, PA.  
MILLVILLE, PA.

1. AM APPLY TRAIL E

2. VALLEY J-W LARE

3. PK

NOTE ELEVATIONS ARE REFERENCED TO DRAINING HIGHWAY  
MILLWAY (BROAD CRESTED DAM) AT ELEVATION 100.15  
THIS SEEMS REASONABLE WHEN EXAMINING THE MAP  
IN. THE LAKE DOES NOT HAVE AN ELEVATION SPECIFIED ON A  
SHEET

EP: INCREASES AS TIME LAST TIME TO PEAK 1.4

$$\begin{aligned} E_p &= \frac{1}{2} (1.4)^{0.3} \\ &= 1.85 (29(0.93))^{0.3} \\ &= 1.65 \text{ HOURS} \end{aligned}$$

### RESERVOIR CAPACITY:

SURFACE AREA AT NORMAL POOL = 330 ACRES  
- SURFACE AREA AT ELEVATION 100.15 (2000)  
'PLANIMETERED' AREA

ASSUME WILKINSON METHOD APPLIES TO THE LAKE  
IN POOL BELOW NORMAL POOL.


VOLUME AT NORMAL POOL = 1.65 HOURS

$$V = 1.65 AH, \quad H = \frac{3V}{A} = 3 \text{ HOURS}$$

2.0 AC STORAGE AT ELEVATION 100.15

MAJOR FORM 2-1-18 MAR 74

ELEVATION (FEET) ABOVE  
AT L.



D-5

TO FIND THE AREA OF THE LAKE  
ASSUME THE AVERAGE AREA  
AREA METHOD - SURFACE TO  
ELEVATIONS ABOVE NORMAL POOL  
ELEVATION

$$AV = \frac{(A_1 + A_2) H}{2}$$

WATERWAY IMPROVEMENT PROJECT

WATERWAY NAME

SHEET 2 OF 6 SHEETS

COMPUTED BY

CHECKED BY

DATE 1-13-81

ELEVATION STORAGE ABLE

ELEVATION (MSL)	AREA (ACRES)	SH (FT)	$\text{AV} = \left( \frac{A_1 + A_2}{2} \right) \Delta H$ (AC-FT)	CUMULATIVE VOLUME (AC-FT)
655.75				30.0
656.75	15	155	5.0	35.0
657.00	20	125	2.1	47.1
657.00	15	100	0.8	57.9
658.00	25	100	2.0	59.9
661.00	35	100	2.8	62.7
662.00	32	100	3.3	66.0
663.00	4	100	0.7	69.7
664.00	4.5	100	1.2	73.9
665.00	5.0	100	1.8	78.7
670.00	6.0	500	77.5	216.2

• THIS AREA FOR THE 5' ABOVE SPILLWAY CREST.

THE DRAINAGE AREA ABOVE DAM IS = 0.52 mi<sup>2</sup>

ELEVATION (MSL)	STORAGE (AC-FT)
655.75	0
656.00	30
656.75	35
658.00	50
659.00	60
660.00	70
661.00	80
662.00	100
663.00	110
664.00	120
665.00	140
670.00	220

THIS DATA TO BE

INPUT TO

BS &amp; BE CARDS.

660.20 = 87 AC-FT

SUBJECT SAFETY ANALYSISCOMPUTATIONS VALLEY VIEW LAKE SHEET 4 OF 12 SHEETSCOMPUTED BY JPB CHECKED BY \_\_\_\_\_ DATE 1-13-81PMF CALCULATIONS:

- APPROXIMATE RAINFALL INDEX = 22.2 INCHES  
CORRESPONDING TO A DURATION OF 24 HOURS AND A  
DRAINAGE AREA OF 200 mi<sup>2</sup> - ALL SEASON ENVELOPE
- SUSQUEHANNA RIVER BASIN - GEOGRAPHIC AREA ADJUSTMENT  
MADE BY HYDROMET 40 - FIGURE 1 IS 100 %.
- DEPTH - REA - DURATION - HYDROMET 40 VALUE
- ASSUME VALUES CORRESPONDING TO A 10 mi<sup>2</sup> AREA MAY BE  
APPLIED TO THIS 0.52 mi<sup>2</sup> AREA

<u>DURATION (HRS)</u>	<u>PERCENT OF INDEX RAINFALL</u>
6	117
12	127
24	136
48	143
72	145

NOTE. HOP BROOK FACTOR IS INTERNALLY COMPUTED BY THE HEC-DB PROGRAM. FOR A DRAINAGE AREA LESS THAN 10 SQUARE MILES, THE ADJUSTMENT FACTOR = 0.80. THIS ADJUSTMENT IS FOR BASIN SHAPE AND FOR THE LESSER LIKLIHOOD OF A SEVERE STORM CENTERING OVER A SMALL BASIN.

SDF BASED ON THE SMALL STORAGE (LESS THAN 80 AC FT) AND SMALL HEIGHT (APPROXIMATELY 20 FEET), THE SDF SELECTED FOR THIS POND WAS 1/2 THE PMF. THIS IS IN ACCORDANCE WITH THE GUIDENCE PROVIDED.

$$\therefore \text{USE } SDF = \frac{1}{2} \text{ PMF}$$

SUBJECT DAW SAFETY ANALYSISCOMPUTATIONS VALLEY VIEW LAKE SHEET 5 OF 16 SHEETSCOMPUTED BY JFB CHECKED BY \_\_\_\_\_ DATE 1-13-81EMERGENCY SPILLWAY CAPACITY:

NOTE: SPILLWAY IS LOCATED NEAR RIGHT ABUTMENT. SEE FIELD SKETCH IN APPENDIX A, EXHIBIT A-1.

SPILLWAY DATA.

TYPE - BROAD CRESTED, 20 FEET WIDE  
LENGTH - 20 FEET


CREST ELEVATION - 656.75

LOW POINT TOP OF DAM - 660.20

SPILLWAY FREEBOARD - 3.5 FEET

C VALUE - 2.80 for spillway  
2.85 for embankment

NOTE: THESE C VALUES WILL BE USED BASED ON WIDTH PARALLEL TO FLOW, SPILLWAY 20 FEET, EMBANKMENT 3 FEET. THESE VALUES WILL BE HELD CONSTANT FOR ALL HEADS, AND WILL BE CONSERVATIVE FOR FACILITY RATING.

SPILLWAY RATING CURVE:

NOTE: ONCE WATER SURFACE ELEVATION REACHES 660.55, STEEL I-BEAMS IN BRIDGE BEGIN TO BLOCK SPILLWAY FLOW AS SHOWN ABOVE. THIS OCCURS FIRST ON LEFT SIDE ON SPILLWAY WHERE BRIDGE SLOPES DOWN ONTO EMBANKMENT.

SUBJECT DAM SAFETY ANALYSISCOMPUTATIONS VALLEY VIEW LAKE SHEET 6 OF 6 SHEETSCOMPUTED BY JPB CHECKED BY \_\_\_\_\_ DATE 1-14-81

SINCE THE LOW POINT TOP OF DAM IS ELEVATION 660.20 AND PRESSURE FLOW WOULD NOT BEGIN IN THE SPILLWAY UNTIL ELEVATION 660.55, FLOW WOULD OVERTOP THE EMBANKMENT BEFORE PRESSURE FLOW WOULD BEGIN IN THE SPILLWAY. THEREFORE, THE SPILLWAY RATING CURVE WAS COMPUTED TO ELEVATION 660.55 AS FREE DISCHARGE, AND THIS VALUE WOULD BE THE MAXIMUM DISCHARGE THAT THE SPILLWAY WOULD PASS.

SPILLWAY RATING CURVERECALL  $C=2.85$ ;  $L=20$  feet

POOL ELEVATION (MSL)	H (ft)	Q (CFS)	ROUNDED Q (CFS)
656.75	0	0	0
657.00	0.25	7.1	10
658.00	1.25	79.6	80
659.00	2.25	192.4	190
660.00	3.25	333.9	330
660.20	3.45	365.3	370
660.55	3.80	422.2	420
665.00	-	-	420

$$Q = CLH^{3/2} \text{ for DISCHARGE VALUES}$$

EMBANKMENT RATING CURVE :

THIS ANALYSIS ASSUMES THAT THE EMBANKMENT BEHAVES AS A BROAD CRESTED WEIR IF OVERTOPPING OCCURS. THIS DISCHARGE CAN BE ESTIMATED BY:

$$Q = CL H_w^{3/2}$$

WHERE :  $Q$  = DISCHARGE OVER EMBANKMENT, IN CFS

$L$  = LENGTH OF EMBANKMENT, FT

$H_w$  = WEIGHTED HEAD, IN FEET, AVERAGE FLOW AREA WEIGHTED ABOVE LOW POINT OF DAM

$C$  = COEFFICIENT OF DISCHARGE



SUBJECT DAM SAFETY ANALYSISCOMPUTATIONS VALLEY VIEW LAKESHEET 7 OF 16 SHEETSCOMPUTED BY JPB

CHECKED BY \_\_\_\_\_

DATE 1-14-81LENGTH OF EMBANKMENT INUNDATED  
VS. RESERVOIR ELEVATION:

<u>RESERVOIR ELEVATION (MSL)</u>	<u>EMBANKMENT LENGTH (FT)</u>
660.20	0
660.55	100
661.00	280
662.00	340
663.00	355
664.00	360 *
665.00	360 *
670.00	360 *

\* - MAXIMUM LENGTH OF EMBANKMENT

EMBANKMENT RATING TABLE:

<u>RESERVOIR ELEVATION (MSL)</u>	<u>L<sub>1</sub> (FT)</u>	<u>L<sub>2</sub> (FT)</u>	<u>INCREMENTAL HEAD, H<sub>i</sub> (FT)</u>	<u>① INCREMENTAL FLOW AREA, A<sub>i</sub> (FT<sup>2</sup>)</u>	<u>TOTAL FLOW AREA, A<sub>T</sub> (FT<sup>2</sup>)</u>	<u>② WEIGHTED HEAD, H<sub>w</sub> (FT)</u>	<u>③ Q (CFS)</u>
660.20	0	0	0	0	0	0	0
660.55	100	0	0.35	17.5	17.5	0.175	21
661.00	280	100	0.45	85.5	103	0.37	178
662.00	340	280	1.00	310.0	413	1.21	1289
663.00	355	340	1.00	347.5	760.5	2.14	3169
664.00	360	355	1.00	357.5	1118.0	3.10	5600
665.00	360	360	1.00	360.0	1478.0	4.10	8517
670.00	360	360	-	1800.0	3278.0	7.10	28160

①  $A_i = H_i [(L_1 + L_2)/2]$

②  $H_w = A_T / L_1$

③  $Q = CL_1 H_w^{3/2}$

recall  $C = 2.85$  from page 5 of this  
appendix

SUBJECT LIA SAFETY ANALYSISCOMPUTATIONS VALLEY VIEW LAKE SHEET 8 OF 16 SHEETSCOMPUTED BY JPLB CHECKED BY \_\_\_\_\_ DATE 1-14-81TOTAL FACILITY RATING CURVE:

RESERVOIR ELEV. (MSL)	Q SALLYWAY (CFS)	Q EMBANKMENT (CFS)	Q TOTAL (CFS)
656.75	0	0	0
657.00	10	0	10
658.00	80	0	80
660.20	370	0	370
660.55	420	20	440
661.00	420	180	600
662.00	420	1300	1720
663.00	420	3170	3590
664.00	420	5600	6020
665.00	420	8520	8940

NOTE: DROP INLET IS ASSUMED BLOCKED FOR FLOOD ROUTING PURPOSES.

THE ABOVE VALUES WILL BE INPUT ON Y4+45 CARDS.

DROP INLET

FIRST WE WILL CALCULATE THE DIAMETER OF THE JET AS THE FLOW FALLS FROM THE INVERT OF DROP INLET - EL. 656 TO THE BOTTOM OF THE 18 inch pipe where it changes to a 10 inch pipe, Elevation 641.0. MAX POOL IS AT 660.20

\* THE DIAMETER OF A JET ISSUING FROM A HORIZONTAL ORIFICE CAN BE DETERMINED FOR ANY POINT BELOW THE WATER SURFACE IF IT IS ASSUMED THAT THE CONTINUITY EQUATION,  $Q = VA$ , IS VALID AND IF FRICTION AND OTHER LOSSES ARE NEGLECTED.

SUBJECT DAM SAFETY ANALYSISCOMPUTATIONS VALLEY VIEW LAKESHEET 9 OF 16 SHEETSCOMPUTED BY JTB

CHECKED BY \_\_\_\_\_

DATE 1-22-81\* FOR A CIRCULAR SET,  $Q = \pi R^2 \sqrt{2gh}$ 

we have an 18" DROP INLET TO AN APPROXIMATE HORIZONTAL 10" LINE.

THE MINIMUM SIZE SHAFT WHICH WILL ACCOMMODATE THE FLOW WITHOUT RESTRICTIONS AND WITHOUT DEVELOPING PRESSURES ALONG THE SIDE OF THE SHAFT. ASSUME SET IS 70% OF PIPE DIA, THEREFORE, FREE FALL WOULD BE APPLICABLE.

$$R = 0.204 \frac{Q^{1/2}}{H_a^{1/4}} \quad \text{where: } H_a = \text{difference in water surface elevation, and elevation under consideration.}$$

$$\therefore Q = \left[ \frac{1}{0.204} R (H_a)^{1/4} \right]^2 = \left[ \frac{1}{0.204} (0.525 \text{ ft}) (19.2 \text{ ft})^{1/4} \right]^2 = 29 \text{ cfs}$$

$$H_a = 660.2 - 641.0 = 19.2 \text{ feet}$$

$$R = \text{radius of set} = 0.7 \left( \frac{18 \text{ in}}{2} \times \frac{\text{ft}}{12 \text{ in}} \right) = 0.525 \text{ feet}$$

NOW CHECKING FOR ORIFICE FLOW IN 10 inch HORIZONTAL LINE

$$Q = CA \sqrt{2gh} \quad C = 0.6 \text{ (A)}$$

$$\therefore Q = 0.6 \left( \pi \left( \frac{5 \text{ in}}{12 \text{ in}} \right)^2 \right) \sqrt{2 \left( 32.2 \frac{\text{ft}}{\text{sec}^2} \right) (19.2 \text{ ft})} = 11.5 \text{ cfs}$$

$\therefore$  LIMITING VALUE AT MAXIMUM POOL IS - 11.5 cfs

$Q = 11.5 \text{ cfs}$  @ MAX. POOL THRU OUTLET

SEE APPENDIX E FOR PLANS OF DROP INLET.

$\therefore Q \approx 12 \text{ cfs}$  AT MAXIMUM POOL (EL. 660.2)

\* FROM - DESIGN OF SMALL DAMS -


① FROM - HANDBOOK OF HYDRAULICS - KING - 1963 - pg - 46

SUBJECT DAM SAFETY ANALYSISCOMPUTATIONS VALLEY VIEW LAKESHEET 10 OF 16 SHEETSCOMPUTED BY GPB

CHECKED BY \_\_\_\_\_

DATE 1-14-81RESULTS OF THE OVERTOPPING ANALYSIS:

AS CAN BE SEEN ON PAGE 4/4 OF THE OVERTOPPING ANALYSIS, THE FOLLOWING CURVE CAN BE DRAWN FROM THE SUMMARY TABLE.




CAN PASS 32% OF THE PMF PRIOR TO OVERTOPPING THE EMANKMENT.

TOP OF DAM ELEVATION IS 660.20

SINCE THE SAF =  $\frac{1}{2}$  THE PMF, THIS FACILITY CAN HANDLE 32% OF THE PMF. SINCE IT IS FELT AT 50% PMF, THE DAM WOULD FAIL DUE TO OVERTOPPING, A BREACH ANALYSIS IS REQUIRED.

BREACH ANALYSIS:

TYPICAL BREACH SECTION



SUBJECT DAM SAFETY ANALYSISCOMPUTATIONS VALLEY VIEW LAKE SHEET 11 OF 16 SHEETSCOMPUTED BY JPB CHECKED BY \_\_\_\_\_ DATE 1-14-81HEC1AB INPUT PARAMETERS FOR BREACH ANALYSIS

FOUR PLANS WILL BE USED FOR A DIRECT COMPARISON OF FAILURE VS. NON-FAILURE CONDITIONS. PARAMETERS ARE AS FOLLOWS.

PLAN NUMBER	BREACH BOTTOM WIDTH (FT)	FULL BREACH DEPTH (FT)	SIDE SLOPES (H on V)	TOTAL BREACH TIME (HRS)
1	-	-	-	-
2	75	13.2	1H on 1V	0.33
3	75	13.2	1H on 1V	1.00
4	75	13.2	1H on 1V	2.00

HEC1AB OUTPUT:

## RESULTS OF DAM BREACH ANALYSIS

AS NOTED ABOVE, PLAN 1 IS FOR NON-FAILURE CONDITIONS.

PLAN NUMBER	MAXIMUM OUTFLOW OVER DAM AND/OR THRU BREACH (CFS)	DOWNSTREAM DAMAGE CENTER #1		DOWNSTREAM DAMAGE CENTER #2	
		STAGE (MSL)	FLOW (CFS)	STAGE (MSL)	FLOW (CFS)
1	516	605.3	507	604.1	507
2	5212	607.9	2345	606.8	2368
3	2288	607.0	1546	605.9	1539
4	1379	606.6	1190	605.4	1187

DOWNSTREAM DAMAGE CENTER #1- DAMAGE ELEV. AT 606


DOWNSTREAM DAMAGE CENTER #2- DAMAGE ELEV. AT 606


SUBJECT DAM SAFETY ANALYSISCOMPUTATIONS VALLEY VIEW LAKE SHEET 12 OF 16 SHEETSCOMPUTED BY JPB CHECKED BY \_\_\_\_\_ DATE 1-16-81

SINCE PLAN 2 INDICATES THAT FAILURE CONDITIONS  
SIGNIFICANTLY INCREASE THE HAZARD TO LOSS OF LIFE  
OR INCREASED PROPERTY DAMAGE, THE SPILLWAY IS  
RATED AS SERIOUSLY INADEQUATE.

EUGENE DIETZGEN CO.  
MADE IN U.S.A.

NO. 340R-20 DIETZGEN GRAPH PAPER  
20 X 20 PER INCH









EUGENE DIETZEN CO.  
MADE IN U. S. A.

NO. 340R-20 DIETZEN GRAPH PAPER  
20 X 20 PER INCH





\*\*\*\*\*  
 FLOOD HYDROGRAPH PACKAGE (HEC-1)  
 DAM SAFETY VERSION JULY 1978  
 LAST MODIFICATION 01 APR 80  
 \*\*\*\*\*

1	A1	VALLEY VIEW LAKE DER NO. 70-19-75									
2	A2	DAM SAFETY INSPECTION PROGRAM 1-14-81									
3	A3	OVERTOPPING ANALYSIS *** PRELIMINARY ***									
4	B	144	0	20	0	0	0	0	0	0	0
5	R1	5	0	0	0	0	0	0	0	0	0
6	J	1	5	1							
7	J1	0.10	0.20	0.30	0.50	1.00					
8	K	0	1	0	0	0	1	0	0	0	0
9	K1	RUNOFF FROM DRAINAGE AREA ABOVE VALLEY VIEW LAKE									
10	H	1	1	0.52	0	0.52	0	0	1	0	
11	P	0	22.2	117	127	136	143	145			
12	T	0	0	0	0	0	0	1.0	0.05	0	0
13	W	1.65	0.50								
14	X	-1.5	-0.05	2							
15	K	1	1	0	0	0	1	0	0	0	0
16	K1	ROUTING ZONE'S THRU VALLEY VIEW LAKE AND SPILLWAY									
17	Y	0	0	0	1	1	0	0	0	0	0
18	Y1	1	0	0	0	0	0	-656.0	-1	0	0
19	Y4	656.0	657.0	658.0	660.2	660.55	661.0	662.0	663.0	664.0	665.0
20	YS	0	10	80	370	440	600	1720	3590	6020	8940
21	SS	0	30	35	50	60	70	80	100	110	140
22	SE	646.50	656.0	656.75	658.0	659.0	660.0	661.0	662.0	663.0	665.0
23	SD	660.2									
24	K	99									

PREVIEW OF SEQUENCE OF STREAM NETWORK CALCULATIONS

RUNOFF HYDROGRAPH AT 1  
 ROUTE HYDROGRAPH TO 1  
 END OF NETWORK

\*\*\*\*\*  
 FLOOD HYDROGRAPH PACKAGE (HEC-1)  
 DAM SAFETY VERSION JULY 1978  
 LAST MODIFICATION 01 APR 80  
 \*\*\*\*\*

RUN DATE: 81/03/05.  
 TIME: 07.14.31.

VALLEY VIEW LAKE DER NO. 70-19-75  
 DAM SAFETY INSPECTION PROGRAM 1-14-81  
 OVERTOPPING ANALYSIS \*\*\* PRELIMINARY \*\*\*

JOB SPECIFICATION										
NO	NHR	NMIN	IDAY	IHR	IMIN	METRC	IPLT	IPRT	NSTAN	
144	0	20	0	0	0	0	0	0	0	
			JOPER	NWT	LROPT	TRACE				
			5	0	0	0				

MULTI-PLAN ANALYSES TO BE PERFORMED  
 NPLAN= 1 NRTIO= 5 LRTIO= 1

RTIOS= .10 .20 .30 .50 1.00

VALLEY VIEW LAKE  
 OVERTOPPING ANALYSIS

\*\*\*\*\*

# SUB-AREA RUNOFF COMPUTATION

RUNOFF FROM DRAINAGE AREA ABOVE VALLEY VIEW LAKE

ISTAG ICOMP IECON ITAPE JPLT JPRT INAME ISTAGE IAUTO  
1 0 0 0 0 0 1 0 0

HYDROGRAPH DATA  
IHYDG IUNG TAREA SNAP TRSDA TRSPC RATIO ISNOW ISAME LOCAL  
1 1 .52 0.00 .52 0.00 0.000 0 1 0

PRECIP DATA  
SPFE PMS R6 R12 R24 R48 R72 R96  
0.00 22.20 117.00 127.00 136.00 143.00 145.00 0.00

TRSPC COMPUTED BY THE PROGRAM IS .800

LOSS DATA  
LROPT STRKR DLTGR RTIOL ERAIN STRKS RTIOK STRTL CNSTL ALSMX RTIMP  
0 0.00 0.00 1.00 0.00 0.00 1.00 1.00 .05 0.00 0.00

UNIT HYDROGRAPH DATA  
TP= 1.65 CP= .50 NTA= 0

RECESSION DATA  
STRTO= -1.50 GRCSN= -.05 RTIOR= 2.00  
APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SNYDER CP AND TP ARE TC= 5.50 AND R= 6.52 INTERVALS

UNIT HYDROGRAPH 38 END-OF-PERIOD ORDINATES, LAG= 1.66 HOURS, CP= .50 VOL= 1.00  
8. 29. 58. 84. 101. 101. 89. 76. 66. 56.  
48. 41. 35. 30. 26. 22. 19. 16. 14. 12.  
10. 9. 8. 7. 6. 5. 4. 4. 3. 3.  
2. 2. 2. 1. 1. 1. 1. 1. 1. 1.

\*\*\*\*\*

## HYDROGRAPH ROUTING

ROUTING ZPHF'S THRU VALLEY VIEW LAKE AND SPILLWAY

ISTAG ICOMP IECON ITAPE JPLT JPRT INAME ISTAGE IAUTO  
1 1 0 0 0 0 1 0 0

ROUTING DATA  
GLOSS CLOSS AVG IRES ISAME IOPT IPMP LSTR  
0.0 0.000 0.00 1 1 0 0 0

NSTPS NSTDL LAG AMSKK X TSK STORA ISPRAT  
1 0 0 0.000 0.000 0.000 -656. -1

STAGE	656.00	657.00	658.00	660.20	660.55	661.00	662.00	663.00	664.00	665.00
FLOW	0.00	10.00	80.00	370.00	440.00	600.00	1720.00	3590.00	6020.00	8940.00
CAPACITY=	0.	30.	35.	50.	60.	70.	80.	100.	110.	140.
ELEVATION=	647.	656.	657.	658.	659.	660.	661.	662.	663.	665.

CREL SPWID COBW EXPW ELEV COOL CAREA EXPL  
656.8 0.0 0.0 0.0 0.0 0.0 0.0 0.0

DAM DATA  
TOPEL COOD EXPD DAMWID  
660.2 0.0 0.0 0.

VALLEY VIEW LAKE

OVERTOPPING ANALYSIS

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

1

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS  
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)  
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS				
				RATIO 1 .10	RATIO 2 .20	RATIO 3 .30	RATIO 4 .50	RATIO 5 1.00
HYDROGRAPH AT	1	.52	1	131.	261.	392.	653.	1306.
	(	1.35)	(	3.70)	7.40)	11.10)	18.50)	36.99)
ROUTED TO	1	.52	1	103.	230.	348.	639.	1289.
	(	1.35)	(	2.91)	6.50)	9.86)	18.10)	36.50)

1

## SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1 .....

ELEVATION  
STORAGE  
OUTFLOWINITIAL VALUE  
656.00  
30.  
0.SPILLWAY CREST  
656.75  
35.  
8.TOP OF DAM  
660.20  
72.  
370.

RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.10	658.17	0.00	52.	103.	0.00	42.67	0.00
.20	659.13	0.00	61.	230.	0.00	42.33	0.00
.30	660.03	0.00	70.	348.	0.00	42.33	0.00
.50	661.04	.84	81.	639.	3.67	41.67	0.00
1.00	661.62	1.42	92.	1289.	6.67	41.33	0.00

\*\*\*\*\*  
 FLOOD HYDROGRAPH PACKAGE (HEC-1)  
 DAM SAFETY VERSION JULY 1978  
 LAST MODIFICATION 01 APR 80  
 \*\*\*\*\*

VALLEY View LAKE  
 OVERTOPPING ANALYSIS

\*\*\*\*\*  
 FLOOD HYDROGRAPH PACKAGE (HEC-1)  
 DAM SAFETY VERSION JULY 1978  
 LAST MODIFICATION 01 APR 80  
 \*\*\*\*\*

1	A1	VALLEY VIEW LAKE DER NO. 70-19-75									
2	A2	DAM SAFETY INSPECTION PROGRAM 1-14-81									
3	A3	BREACHING ANALYSIS *** PRELIMINARY ***									
4	B	144	0	15	0	0	0	0	0	0	0
5	B1	5	0	0	0	0	0	0	0	0	0
6	J	4	1	1							
7	J1	0.42									
8	K	0	1	0	0	0	0	1	0	0	0
9	K1	RUNOFF FROM DRAINAGE AREA ABOVE VALLEY VIEW LAKE									
10	M	1	1	0.52	0	0.52	0	0	0	1	0
11	P	0	22.2	117	127	136	143	145			
12	T	0	0	0	0	0	0	1.0	0.05	0	0
13	W	1.65	0.50								
14	X	-1.5	-0.05	2							
15	K	1	1	0	0	0	0	1	0	0	0
16	K1	ROUTING XPMF'S THRU VALLEY VIEW LAKE AND SPILLWAY									
17	Y	0	0	0	1	0	0	0	0	0	0
18	Y1	1	0	0	0	0	0	-656.0	-1	0	0
19	Y4	656.0	657.0	658.0	660.2	660.55	661.0	662.0	663.0	664.0	665.0
20	Y5	0	10	80	370	440	600	1720	3590	6020	8940
21	Y6	0	30	35	50	60	70	80	100	110	140
22	Y7	646.50	656.0	656.75	658.0	659.0	660.0	661.0	662.0	663.0	665.0
23	Y8	656.75									
24	Y9	660.2									
25	Y10	75	1	647	0.33	656.75	670				
26	Y11	75	1	647	0.33	656.75	660.7				
27	Y12	75	1	647	1.00	656.75	660.7				
28	Y13	75	1	647	2.00	656.75	660.7				
29	K	1	2	0	0	0	0	1			
30	K1	ROUTE FLOWS THRU 1ST DOWNSTREAM CROSS SECTION (SPILLWAY)									
31	Y	0	0	0	1	1	0	0			
32	Y1	1	0	0	0	0	0	0			
33	Y6	0.07	0.05	0.07	647.5	664	40	0.25			
34	Y7	100	664	117	661	150	651.4	155	647.5	165	647.5
35	Y7	170	651.4	178	656	195	664				
36	K	1	3	0	0	0	0	1			
37	K1	ROUTE FLOWS THRU 2ND DOWNSTREAM CROSS SECTION									
38	Y	0	0	0	1	1	0	0			
39	Y1	1	0	0	0	0	0	0			
40	Y6	0.07	0.05	0.07	641.8	654	110	0.052			
41	Y7	100	654	120	648	133	644	140	641.8	165	641.8
42	Y7	170	644	205	649	238	654				
43	K	1	4	0	0	0	0	1			
44	K1	ROUTE FLOWS THRU 3RD DOWNSTREAM CROSS SECTION (SPILLWAY)									
45	Y	0	0	0	1	1	0	0			
46	Y1	1	0	0	0	0	0	0			
47	Y6	0.07	0.05	0.07	640	652	150	0.012			
48	Y7	100	652	115	650	125	648	140	640	200	640
49	Y7	240	644	282	648	324	652				
50	K	1	5	0	0	0	0	1			
51	K1	1ST DOWNSTREAM CROSS SECTION **DAMAGE CENTER**									
52	Y	0	0	0	1	1	0	0			
53	Y1	1	0	0	0	0	0	0			
54	Y6	0.07	0.05	0.07	602	611	4400	0.0086			
55	Y7	100	611	200	606	220	605	225	602	245	602
56	Y7	248	604	323	606	350	611				
57	K	1	6	0	0	0	0	1			
58	K1	2ND DOWNSTREAM CROSS SECTION **DAMAGE CENTER**									
59	Y	0	0	0	1	1	0	0			
60	Y1	1	0	0	0	0	0	0			
61	Y6	0.07	0.05	0.07	601	611	100	0.01			
62	Y7	100	611	162	605	183	603	188	601	208	601
63	Y7	213	603	290	606	318	611				
64	K	99									

PREVIEW OF SEQUENCE OF STREAM NETWORK CALCULATIONS

RUNOFF HYDROGRAPH AT	1
ROUTE HYDROGRAPH TO	1
ROUTE HYDROGRAPH TO	2
ROUTE HYDROGRAPH TO	3
ROUTE HYDROGRAPH TO	4
ROUTE HYDROGRAPH TO	5
ROUTE HYDROGRAPH TO	6
END OF NETWORK	

\*\*\*\*\*  
 FLOOD HYDROGRAPH PACKAGE (HEC-1)  
 DAM SAFETY VERSION JULY 1978  
 LAST MODIFICATION 01 APR 80

DAM BREACH DATA

DAM BREACH DATA					
BRWID	Z	ELBM	TFAIL	WSEL	FAILEL
75.	1.00	647.00	.33	656.75	670.00

STATION 1, PLAN 1, RATIO 1

END-OF-PERIOD HYDROGRAPH ORDINATES

PEAK OUTFLOW IS 516. AT TIME 42.00 HOURS

DAM BREACH DATA

DAM BREACH DATA					
BRWID	Z	ELBM	TFAIL	WSEL	FAILEL
75.	1.00	647.00	.33	656.75	660.70

STATION 1, PLAN 2, RATIO 1

BEGIN DAM FAILURE AT 41.75 HOURS

PEAK OUTFLOW IS 5215. AT TIME 42.05 HOURS

( !

DAM BREACH DATA					
BRWID	Z	ELBM	TFAIL	WSEL	FAILEL
75.	1.00	647.00	1.00	656.75	660.70

STATION 1, PLAN 3, RATIO 1

PEAK OUTFLOW IS 2295. AT TIME 42.44 HOURS

DAM BREACH DATA					
BRWID	Z	ELBM	TFAIL	WSEL	FAILEL
75.	1.00	647.00	2.00	656.75	660.70

STATION 1, PLAN 4, RATIO 1

PEAK OUTFLOW IS 1384. AT TIME 42.96 HOURS

VALLEY VIEW LAKE

BREACH ANALYSIS

PAGE 2/10

D. 24

ISTAG 2 ICOMP 1 IECON 0 ITAPE 0 JPLT 0 JPRT 0 INAME 1 ISTAGE 0 IAUTO 0

GLOSS	CLOSS	AVG	IRIS	ISAME	IOPT	IPMP		LSTR
0.0	0.000	0.00	1	1	0	0		0
	NSTPS	NSTOL	LAG	AMSKK	X	TSK	STORA	ISPRAT
	1	0	0	0.000	0.000	0.000	0.	0

GN(1)	GN(2)	GN(3)	ELNVT	ELMAX	RLNTH	SEL
.0700	.0500	.0700	647.5	664.0	40.	.25000

100.00	664.00	117.00	661.00	150.00	651.40	155.00	647.50	165.00	647.50
170.00	651.40	178.00	656.00	195.00	664.00				

STORAGE	0.00 .20	.01 .23	.02 .28	.03 .32	.05 .37	.06 .42	.08 .48	.11 .54	.13 .61	.16 .68
OUTFLOW	0.00 9315.85	118.98 11519.25	387.85 14017.07	789.21 16825.14	1325.13 19958.85	2074.59 23433.15	3072.23 27189.78	4277.73 31263.85	5709.50 35774.01	7384.11 40740.05
STAGE	647.50 656.18	648.37 657.05	649.24 657.92	650.11 658.79	650.97 659.66	651.84 660.53	652.71 661.39	653.58 662.26	654.45 663.13	655.32 664.00
FLOW	0.00 9315.85	118.98 11519.25	387.85 14017.07	789.21 16825.14	1325.13 19958.85	2074.59 23433.15	3072.23 27189.78	4277.73 31263.85	5709.50 35774.01	7384.11 40740.05

+++++                      +++++                      +++++                      +++++                      +++++

```

ISTAG  ICOMP  IECON  ITAPE  JPLT  JPRT  INAME  ISTAGE  IAUTO
   3      1      0      0      0      0      1      0      0

```

ROUTING DATA								
GLOSS	CLOSS	AVG	IRIS	ISAME	IOPT	IPMP		LSTR
0.0	0.000	0.00	1	1	0	0		0
	NSTPS	NSTDL	LAG	AMSKY	X	TSK	STORA	ISPRAT
	1	0	0	0.000	0.000	0.000	0.	0

GN(1)	GN(2)	GN(3)	ELNVT	ELMAX	RLNTH	SEL
.0700	.0500	.0700	641.8	654.0	110.	.05200

100.00	654.00	120.00	648.00	133.00	644.00	140.00	641.80	165.00	641.80
170.00	644.00	205.00	649.00	238.00	654.00				

STORAGE	0.00 .80	.04 .93	.09 1.08	.15 1.24	.21 1.40	.28 1.58	.36 1.77	.45 1.97	.56 2.17	.67 2.39
OUTFLOW	0.00 5717.62	82.83 6960.12	269.41 8347.04	543.91 9880.67	931.66 11565.04	1439.06 13404.90	2054.95 15404.98	2785.22 17569.97	3635.46 19904.49	4611.18 22413.12
STAGE	641.80 648.22	642.44 648.86	643.08 649.51	643.73 650.15	644.37 650.79	645.01 651.43	645.65 652.07	646.29 652.72	646.94 653.36	647.58 654.00
	0.00	0.00	269.41	543.91	931.66	1439.06	2054.95	2785.22	3635.46	4611.18

## BREACH ANALYSIS

Page 3/7



\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

## HYDROGRAPH ROUTING

ROUTE FLOWS THRU 3RD DOWNSTREAM CROSS SECTION (SPILLWAY)

ISTAG	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
4	1	0	0	0	0	1	0	0

ALL PLANS HAVE SAME  
ROUTING DATA

GLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	LSTR
0.0	0.000	0.00	1	1	0	0	0
NSTPS	NSTDIL	LAG	AMSKK	X	TSK	STORA	ISPRAT
1	0	0	0.000	0.000	0.000	0.	0

## NORMAL DEPTH CHANNEL ROUTING

GN(1)	GN(2)	GN(3)	ELNVT	ELMAX	RLNTH	SEL
.0700	.0500	.0700	640.0	652.0	150.	.01200

CROSS SECTION COORDINATES—STA.ELEV.STA.ELEV—ETC

	100.00	652.00	115.00	650.00	125.00	648.00	140.00	640.00	200.00	640.00
	240.00	644.00	282.00	648.00	324.00	652.00				
STORAGE	0.00	.14	.29	.46	.65	.86	1.08	1.31	1.57	1.84
	2.13	2.43	2.75	3.09	3.45	3.83	4.23	4.66	5.11	5.58
OUTFLOW	0.00	92.96	302.16	609.17	1010.34	1505.75	2097.10	2847.88	3734.04	4727.86
	5830.95	7044.90	8371.37	9835.42	11467.68	13228.10	15120.08	17147.00	19315.78	21630.77
STAGE	640.00	640.63	641.26	641.89	642.53	643.16	643.79	644.42	645.05	645.68
	646.32	646.95	647.58	648.21	648.84	649.47	650.11	650.74	651.37	652.00
FLOW	0.00	92.96	302.16	609.17	1010.34	1505.75	2097.10	2847.88	3734.04	4727.86
	5830.95	7044.90	8371.37	9835.42	11467.68	13228.10	15120.08	17147.00	19315.78	21630.77

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

## HYDROGRAPH ROUTING

1ST DOWNSTREAM CROSS SECTION \*\*DAMAGE CENTER\*\*

ISTAG	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
5	1	0	0	0	0	1	0	0

ALL PLANS HAVE SAME  
ROUTING DATA

GLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	LSTR
0.0	0.000	0.00	1	1	0	0	0
NSTPS	NSTDIL	LAG	AMSKK	X	TSK	STORA	ISPRAT
1	0	0	0.000	0.000	0.000	0.	0

## NORMAL DEPTH CHANNEL ROUTING

GN(1)	GN(2)	GN(3)	ELNVT	ELMAX	RLNTH	SEL
.0700	.0500	.0700	602.0	611.0	4400.	.00860

VALLEY VIEW LAKE

BREACH ANALYSIS

page 4/7

CROSS SECTION COORDINATES—STA.ELEV.STA.ELEV—ETC

	100.00	611.00	200.00	606.00	220.00	605.00	225.00	602.00	245.00	602.00
	248.00	604.00	323.00	606.00	350.00	611.00				
STORAGE	0.00	.99	2.06	3.19	4.40	5.93	8.32	11.70	16.35	22.20
	28.69	35.76	43.40	51.62	60.42	69.79	79.74	90.26	101.36	113.03
OUTFLOW	0.00	15.98	51.10	101.32	165.31	247.15	354.39	500.80	696.08	959.11
	1291.05	1683.56	2137.88	2655.57	3238.41	3888.30	4607.22	5397.17	6260.19	7198.34
STAGE	602.00	602.47	602.95	603.42	603.89	604.37	604.84	605.32	605.79	606.26
	606.74	607.21	607.68	608.16	608.63	609.11	609.58	610.05	610.53	611.00

D-26

~~~~~

## 2ND DOWNSTREAM CROSS SECTION \*\* DAMAGE CENTER \*\*

| ALL PLANS HAVE SAME ROUTING DATA |       |       |      |       |       |       |       |        |
|----------------------------------|-------|-------|------|-------|-------|-------|-------|--------|
| GLOSS                            | CLOSS | AVG   | IRES | ISAME | IOPT  | IPMP  |       | LSTR   |
| 0.0                              | 0.000 | 0.00  | 1    | 1     | 0     | 0     |       | 0      |
|                                  | NSTPS | NSTDL | LAG  | AMSKK | X     | TSK   | STORA | ISPRAT |
|                                  | 1     | 0     | 0    | 0.000 | 0.000 | 0.000 | 0     | 0      |

|       |       |       |       |       |       |        |
|-------|-------|-------|-------|-------|-------|--------|
| GN(1) | GN(2) | GN(3) | ELNVT | ELMAX | RLNTH | SEL    |
| .0700 | .0500 | .0700 | 601.0 | 611.0 | 100.  | .01000 |

| ROSS   | SECTION | COORDINATES | STATELEV | STATELEV | ETC    |        |        |        |        |
|--------|---------|-------------|----------|----------|--------|--------|--------|--------|--------|
| 100.00 | 611.00  | 162.00      | 605.00   | 183.00   | 603.00 | 188.00 | 601.00 | 208.00 | 601.00 |
| 213.00 | 603.00  | 290.00      | 606.00   | 318.00   | 611.00 |        |        |        |        |

|         |                  |                  |                  |                   |                   |                   |                   |                   |                    |                    |
|---------|------------------|------------------|------------------|-------------------|-------------------|-------------------|-------------------|-------------------|--------------------|--------------------|
| STORAGE | 0.00<br>.78      | .03<br>.96       | .05<br>1.14      | .09<br>1.34       | .12<br>1.55       | .17<br>1.77       | .25<br>2.00       | .35<br>2.23       | .47<br>2.48        | .61<br>2.74        |
| OUTFLOW | 0.00<br>1836.81  | 20.82<br>2368.91 | 67.55<br>2975.98 | 136.04<br>3658.21 | 228.13<br>4416.25 | 358.93<br>5251.02 | 531.92<br>6163.62 | 756.82<br>7155.29 | 1041.98<br>8227.37 | 1394.93<br>9381.25 |
| STAGE   | 601.00<br>606.26 | 601.53<br>606.79 | 602.05<br>607.32 | 602.58<br>607.84  | 603.11<br>608.37  | 603.63<br>608.89  | 604.16<br>609.42  | 604.68<br>609.95  | 605.21<br>610.47   | 605.74<br>611.00   |
| FLOW    | 0.00<br>1836.81  | 20.82<br>2368.91 | 67.55<br>2975.98 | 136.04<br>3658.21 | 228.13<br>4416.25 | 358.93<br>5251.02 | 531.92<br>6163.62 | 756.82<br>7155.29 | 1041.98<br>8227.37 | 1394.93<br>9381.25 |

+++++                      +++++                      +++++                      +++++                      +++++

1

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS:  
FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)  
AREA IN SQUARE MILES (SQUARE KILOMETERS)

| OPERATION     | STATION | AREA           | PLAN | RATIO              | ROUTED TO | 3 | .52<br>( 1.35) | 1 | 516.<br>( 14.61)   |
|---------------|---------|----------------|------|--------------------|-----------|---|----------------|---|--------------------|
| HYDROGRAPH AT | 1       | .52<br>( 1.35) | 1    | 547.<br>( 15.50)   |           |   |                | 2 | 4194.<br>( 118.76) |
|               |         |                | 2    | 547.<br>( 15.50)   |           |   |                | 3 | 1796.<br>( 50.85)  |
|               |         |                | 3    | 547.<br>( 15.50)   |           |   |                | 4 | 1318.<br>( 37.31)  |
|               |         |                | 4    | 547.<br>( 15.50)   | ROUTED TO | 4 | .52<br>( 1.35) | 1 | 516.<br>( 14.60)   |
| ROUTED TO     | 1       | .52<br>( 1.35) | 1    | 516.<br>( 14.61)   |           |   |                | 2 | 4073.<br>( 115.34) |
|               |         |                | 2    | 4249.<br>( 120.31) |           |   |                | 3 | 1809.<br>( 51.21)  |
|               |         |                | 3    | 1790.<br>( 50.69)  |           |   |                | 4 | 1314.<br>( 37.21)  |
|               |         |                | 4    | 1319.<br>( 37.35)  | ROUTED TO | 5 | .52<br>( 1.35) | 1 | 507.<br>( 14.36)   |
| ROUTED TO     | 2       | .52<br>( 1.35) | 1    | 516.<br>( 14.60)   |           |   |                | 2 | 2345.<br>( 66.40)  |
|               |         |                | 2    | 4241.<br>( 120.08) |           |   |                | 3 | 1546.<br>( 43.77)  |
|               |         |                | 3    | 1791.<br>( 50.71)  |           |   |                | 4 | 1190.<br>( 33.70)  |
|               |         |                | 4    | 1319.<br>( 37.34)  | ROUTED TO | 6 | .52<br>( 1.35) | 1 | 507.<br>( 14.36)   |
| VIEW LAKE     |         |                |      |                    |           |   |                | 2 | 2368.<br>( 67.04)  |
| WASH AWAYS    |         |                |      |                    |           |   |                | 3 | 1539.<br>( 43.85)  |

VALLEY VIEW LAKE

## BREACH ANALYSIS

page 5/7

D-2.7

## SUMMARY OF DAM SAFETY ANALYSIS

| PLAN 1 ..... | ELEVATION<br>STORAGE<br>OUTFLOW | INITIAL VALUE<br>656.75<br>35.<br>8. | SPILLWAY CREST<br>656.75<br>35.<br>8. | TOP OF DAM<br>660.20<br>72.<br>370. |                           |                               |                                 |
|--------------|---------------------------------|--------------------------------------|---------------------------------------|-------------------------------------|---------------------------|-------------------------------|---------------------------------|
|              | RATIO<br>OF<br>PMF              | MAXIMUM<br>RESERVOIR<br>W.S.ELEV     | MAXIMUM<br>DEPTH<br>OVER DAM          | MAXIMUM<br>STORAGE<br>AC-FT         | MAXIMUM<br>OUTFLOW<br>CFS | DURATION<br>OVER TOP<br>HOURS | TIME OF<br>MAX OUTFLOW<br>HOURS |
|              | .42                             | 660.76                               | .56                                   | 78.                                 | 516.                      | 3.00                          | 42.00                           |
| PLAN 2 ..... | ELEVATION<br>STORAGE<br>OUTFLOW | INITIAL VALUE<br>656.75<br>35.<br>8. | SPILLWAY CREST<br>656.75<br>35.<br>8. | TOP OF DAM<br>660.20<br>72.<br>370. |                           |                               |                                 |
|              | RATIO<br>OF<br>PMF              | MAXIMUM<br>RESERVOIR<br>W.S.ELEV     | MAXIMUM<br>DEPTH<br>OVER DAM          | MAXIMUM<br>STORAGE<br>AC-FT         | MAXIMUM<br>OUTFLOW<br>CFS | DURATION<br>OVER TOP<br>HOURS | TIME OF<br>MAX OUTFLOW<br>HOURS |
|              | .42                             | 660.76                               | .56                                   | 78.                                 | 5215.                     | 1.14                          | 42.05                           |
| PLAN 3 ..... | ELEVATION<br>STORAGE<br>OUTFLOW | INITIAL VALUE<br>656.75<br>35.<br>8. | SPILLWAY CREST<br>656.75<br>35.<br>8. | TOP OF DAM<br>660.20<br>72.<br>370. |                           |                               |                                 |
|              | RATIO<br>OF<br>PMF              | MAXIMUM<br>RESERVOIR<br>W.S.ELEV     | MAXIMUM<br>DEPTH<br>OVER DAM          | MAXIMUM<br>STORAGE<br>AC-FT         | MAXIMUM<br>OUTFLOW<br>CFS | DURATION<br>OVER TOP<br>HOURS | TIME OF<br>MAX OUTFLOW<br>HOURS |
|              | .42                             | 660.76                               | .56                                   | 78.                                 | 2295.                     | 1.31                          | 42.44                           |
| PLAN 4 ..... | ELEVATION<br>STORAGE<br>OUTFLOW | INITIAL VALUE<br>656.75<br>35.<br>8. | SPILLWAY CREST<br>656.75<br>35.<br>8. | TOP OF DAM<br>660.20<br>72.<br>370. |                           |                               |                                 |
|              | RATIO<br>OF<br>PMF              | MAXIMUM<br>RESERVOIR<br>W.S.ELEV     | MAXIMUM<br>DEPTH<br>OVER DAM          | MAXIMUM<br>STORAGE<br>AC-FT         | MAXIMUM<br>OUTFLOW<br>CFS | DURATION<br>OVER TOP<br>HOURS | TIME OF<br>MAX OUTFLOW<br>HOURS |
|              | .42                             | 660.76                               | .56                                   | 78.                                 | 1384.                     | 1.50                          | 42.96                           |

VALLEY  
VIEW  
LAKE  
DAM

| PLAN 1 |                  | STATION          | 2          | PLAN 1 |                  | STATION          | 3          |
|--------|------------------|------------------|------------|--------|------------------|------------------|------------|
| RATIO  | MAXIMUM FLOW,CFS | MAXIMUM STAGE,FT | TIME HOURS | RATIO  | MAXIMUM FLOW,CFS | MAXIMUM STAGE,FT | TIME HOURS |
| .42    | 516.             | 649.5            | 42.00      | .42    | 516.             | 643.7            | 42.00      |
| PLAN 2 |                  | STATION          | 2          | PLAN 2 |                  | STATION          | 3          |
| RATIO  | MAXIMUM FLOW,CFS | MAXIMUM STAGE,FT | TIME HOURS | RATIO  | MAXIMUM FLOW,CFS | MAXIMUM STAGE,FT | TIME HOURS |
| .42    | 4241.            | 653.6            | 42.00      | .42    | 4194.            | 647.3            | 42.00      |
| PLAN 3 |                  | STATION          | 2          | PLAN 3 |                  | STATION          | 3          |
| RATIO  | MAXIMUM FLOW,CFS | MAXIMUM STAGE,FT | TIME HOURS | RATIO  | MAXIMUM FLOW,CFS | MAXIMUM STAGE,FT | TIME HOURS |
| .42    | 1791.            | 651.5            | 42.50      | .42    | 1796.            | 645.4            | 42.50      |
| PLAN 4 |                  | STATION          | 2          | PLAN 4 |                  | STATION          | 3          |
| RATIO  | MAXIMUM FLOW,CFS | MAXIMUM STAGE,FT | TIME HOURS | RATIO  | MAXIMUM FLOW,CFS | MAXIMUM STAGE,FT | TIME HOURS |
| .42    | 1319.            | 651.0            | 43.00      | .42    | 1319.            | 648.0            | 42.00      |

VALLEY VIEW LAKE

BREACH ANALYSIS

page 6/7

| PLAN 1 |                   | STATION 4         |            |
|--------|-------------------|-------------------|------------|
| RATIO  | MAXIMUM FLOW, CFS | MAXIMUM STAGE, FT | TIME HOURS |
| .42    | 516.              | 641.7             | 42.00      |

| PLAN 2 |                   | STATION 4         |            |
|--------|-------------------|-------------------|------------|
| RATIO  | MAXIMUM FLOW, CFS | MAXIMUM STAGE, FT | TIME HOURS |
| .42    | 4073.             | 645.3             | 42.00      |

| PLAN 3 |                   | STATION 4         |            |
|--------|-------------------|-------------------|------------|
| RATIO  | MAXIMUM FLOW, CFS | MAXIMUM STAGE, FT | TIME HOURS |
| .42    | 1809.             | 643.5             | 42.50      |

| PLAN 4 |                   | STATION 4         |            |
|--------|-------------------|-------------------|------------|
| RATIO  | MAXIMUM FLOW, CFS | MAXIMUM STAGE, FT | TIME HOURS |
| .42    | 1314.             | 642.9             | 43.00      |

| PLAN 1 |                   | STATION 5         |            |
|--------|-------------------|-------------------|------------|
| RATIO  | MAXIMUM FLOW, CFS | MAXIMUM STAGE, FT | TIME HOURS |
| .42    | 507.              | 605.3             | 42.25      |

| PLAN 2 |                   | STATION 5         |            |
|--------|-------------------|-------------------|------------|
| RATIO  | MAXIMUM FLOW, CFS | MAXIMUM STAGE, FT | TIME HOURS |
| .42    | 2345.             | 607.9             | 42.25      |

| PLAN 3 |                   | STATION 5         |            |
|--------|-------------------|-------------------|------------|
| RATIO  | MAXIMUM FLOW, CFS | MAXIMUM STAGE, FT | TIME HOURS |
| .42    | 1546.             | 607.0             | 42.50      |

| PLAN 4 |                   | STATION 5         |            |
|--------|-------------------|-------------------|------------|
| RATIO  | MAXIMUM FLOW, CFS | MAXIMUM STAGE, FT | TIME HOURS |
| .42    | 1190.             | 606.6             | 43.00      |

| PLAN 1 |                   | STATION 6         |            |
|--------|-------------------|-------------------|------------|
| RATIO  | MAXIMUM FLOW, CFS | MAXIMUM STAGE, FT | TIME HOURS |
| .42    | 507.              | 604.1             | 42.25      |

| PLAN 2 |                   | STATION 6         |            |
|--------|-------------------|-------------------|------------|
| RATIO  | MAXIMUM FLOW, CFS | MAXIMUM STAGE, FT | TIME HOURS |
| .42    | 2368.             | 606.8             | 42.25      |

| PLAN 3 |                   | STATION 6         |            |
|--------|-------------------|-------------------|------------|
| RATIO  | MAXIMUM FLOW, CFS | MAXIMUM STAGE, FT | TIME HOURS |
| .42    | 1539.             | 605.9             | 42.50      |

| PLAN 4 |                   | STATION 6         |            |
|--------|-------------------|-------------------|------------|
| RATIO  | MAXIMUM FLOW, CFS | MAXIMUM STAGE, FT | TIME HOURS |
| .42    | 1187.             | 605.4             | 43.00      |

STATION 5 =  
DOWNSTREAM  
DAMAGE CENTER #1  
DAMAGE AT  
ELEV. 606.0

STATION 6 =

DOWNSTREAM  
DAMAGE CENTER #2  
DAMAGE AT  
ELEV. 606.0

RECALL:

PLAN 1 = NO. 1 FAILURE

ALL OTHER PLANS ARE  
BREAK CONDITIONS.


\*\*\*\*\*  
FLOOD HYDROGRAPH PACKAGE (HEC-1)  
DAM SAFETY VERSION JULY 1978  
LAST MODIFICATION 01 APR 80  
\*\*\*\*\*

VALLEY VIEW LAKE  
BREACH ANALYSIS

page 7/7

APPENDIX E

PLATES



LAIRDSVILLE, PA.  
NE/4 HUGHESVILLE 15 QUADRANGLE  
N4107 5—W7630/7.5  
1968  
AMS 5666 II NE. SERIES V831



- ⊙ Centroid of Drainage Area
- Downstream Flood Area
- Longest Watercourse

MILLVILLE, PA.

N4100—W7630/7.5

1968  
PHOTOREVISED 1975  
AMS 5666 II SE. SERIES V831

SCALE 1"=1000'

GREENWOOD

Drainage Boundary

BDY

Millville

Millville

Valley View Lake

Valley View Dam


DC1/DC2

DC1/DC2

PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM  
VALLEY VIEW LAKE DAM  
VALLEY VIEW LAKE ASSN.  
DRAINAGE AREA & DOWNSTREAM  
DEVELOPMENT PLAN  
PLATE E-II

## General Plan

Revised May 26, 1958



Eleu 650.0

Elev 648.5



State Flat  
Spillway  
75  
Wall  
Long  
Wall  
High

Flow Direction

660


65

Flow line  
Crest of d  
Top of

Rubble stone  
Apenn  
6"-10" thick


Heavy Seeded  
Area

Grade of Waterway  
10' in 150'



low line elev 656.0  
↓  
top of dam elev 661.25  
↓  
top of core elev 656.0  
↓

Station 1+30



650


099

PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM  
VALLEY VIEW LAKE DAM  
VALLEY VIEW LAKE ASSN.

PLATE E-III

# Longitudinal Section

Scale - 1" = 10'



CONTINUED FROM THE PREVIOUS PAGE

for 25' 11"

Loam 648.05  
Elev 698.0

+90 +80 +70 +60 +50 +40 +30 +20 +10

647.05

3" Loam  
12" Loam + clay  
20" Clay

695.25

649.75

644.25

693.95

643.05

639.55

636.30

640.45

690.35

Hard shale

6" Loam  
12" Loam + clay  
18" Clay

Station

+10

+90

+80

+70

+60

+50

+40

+30

690.35

690.35

690.05

690.35

690.45

690.75

693.50

Elev 692.0

695.20


696.05

650.00

shale

Loam + Clay

6" Loam  
12" Loam + clay  
70% clay



PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM  
VALLEY VIEW LAKE DAM  
VALLEY VIEW LAKE ASSN.

PLATE E-IV

Cross Section  
 Station 1+30  
 Scale  $\frac{1}{4}'' = 1 \text{ ft.}$

Revised May 8, 1958

Rubble Gutter to old stream  
 Bed - App 10-12" x 9' x 10' long

|                |     |
|----------------|-----|
| SEE REPORT NO. | FOR |
| REG'D          |     |

|                                                                                                                           |             |
|---------------------------------------------------------------------------------------------------------------------------|-------------|
| RECEIVED IN THE OFFICE OF THE ASSISTANT<br>COMMISSIONER OF THE DEPARTMENT OF<br>AGRICULTURE AND FORESTRY<br>ALBANY, N. Y. | FILE NUMBER |
|---------------------------------------------------------------------------------------------------------------------------|-------------|

Slope 3




Elev crest 661.25

Sealed Slope Crest

31  
Outlet pipe to be set  
on 6" x 24" wide concrete  
chadle + enclosed on  
slab set top with 6" concrete

Elev 441.0

Station 1+30



Isolated timber  
piling with 4x4s

90-lb chain-link  
square trash rack  
App 4' x 4' Extending  
1ft below + 2ft above  
water level

EL water line 656.0

Slope 3-1


Welded T Joint

10" or 12" Steel oil line

*will. J. wall*

Concrete head wall  
6'11" x 4'1" x 3' high

EO 12958  
CLASSIFIED  
DATE 10/1/00  
BY 1043



Elev 646.5



Brass gate valve  
with hange wheel  
control

PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM  
VALLEY VIEW LAKE DAM  
VALLEY VIEW LAKE ASSN.  
PLATE E-V




200'

260'

1100'

Elev 644.50 +

00 gal.



PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM  
VALLEY VIEW LAKE DAM  
VALLEY VIEW LAKE ASSN.

PLATE E-VI

APPENDIX F

GEOLOGY



## GENERAL GEOLOGY

Bedrock at Valley View Lake (Northeast quadrant, Millville, Pa 7 1/2-minute quadrangle) is the Mahantango Formation. It is dark gray, silty claystone in poorly defined, massive beds 3 to 10 feet thick containing calcareous zones and pyrite, siderite and limestone nodules. At the dam site, beds are nearly flat lying, dipping only 3° to 5° from the horizontal. Joints are well developed and closely spaced. The formation is moderately to poorly resistant with the rock weathering to splintery and slabby fragments. Unconsolidated material overlying bedrock is glacial till along with weathered material from adjacent bedrock units with a combined thickness no greater than 10 feet at the dam. At the head of the lake bedrock is exposed.

### LEGEND (Bedrock)

Dmh Mahantango Formation

Gray, brown, and olive shale and silty claystone with some limestone and calcareous shale. A thin, resistant sandstone occurs near the middle of the formation in some areas.

Dtr Trimmers Rock Formation

Olive-gray siltstone and shale characterized by graded bedding; contains beds of fine-grained sandstone in some areas.

AD-A099 057 CORPS OF ENGINEERS BALTIMORE MD BALTIMORE DISTRICT F/0 13/13  
NATIONAL DAM INSPECTION PROGRAM. VALLEY VIEW LAKE DAM (NDI ID N--ETC(U)  
FEB 81

CORPS OF ENGINEERS BALTIMORE MD BALTIMORE DISTRICT F/0 13/13  
NATIONAL DAM INSPECTION PROGRAM, VALLEY VIEW LAKE DAM (NDI ID N--ETC(U)  
FEB 81

F/0 13/13

UNCLASSIFIED

NL

2 of 2  
3059147

END

DATE \_\_\_\_\_

FILME

FILED  
AUG 29 1964

55

DTIC

